

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner

\$7.00 LAND CORNER

\$2.00 HSSR

5/4/1997 2:21:32 PM

Receipt #294

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 77

Register of Deeds Stamp & File Number

For corners in

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T46N R2W	E-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

I, William L. Karr, in a field survey on December 17, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-9) Section Corner Common to Sections 20, 21, 28 & 29, T. 46 N., R. 2 W.

1849 H. Mellen set maple post for the section corner.
Witnesses: Maple 6 N 13° E 40 lks
Yellow Birch S 77° W 45 lks

1916 F.H. Brown in Section Drawing Book in County Surveyors Office Brown states that the section corner was lost and he did not replace it.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-9) Section Corner Common to Sections 20, 21, 28 & 29, T. 46 N., R. 2 W.

This corner is being reestablished as part of the Chippewa County Remonumentation Program.

Found no evidence of original corner or subsequent restoration. Reestablished the position at the intersection of the remains of an old North-South fence line and the extension of a road centerline to the East. Distance North is 5222.34'; Distance West is 5307.18'; Distance East is 5218.71'; There are significant ravines to the North and West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-9) Section Corner Common to Sections 20, 21, 28 & 29, T. 46 N., R. 2 W.

Corner is a 3/4" iron with Chippewa County Remonumentation Cap. The corner falls on the Southeast side of a fence post, along an old North-South fence line, at the West edge of a field.

Witnesses: 1" Galvanized Pipe with Pipe Cap S 45° E 45.00'
4" Balsam Fir S 69° W 81.76'
5" Balsam Fir N 60° W 23.91'
6" Balsam Fir N 04° W 14.19'

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by William L. Karr

Date 12-30-96

Surveyor's Michigan License No. 27450

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 26, 1975

REVISED MAY 14, 1975

REVISED JAN 29, 1983

REVISED OCT 1, 1995

BOOK 10 PAGE

BOOK 10 PAGE 77

