

CHIPPEWA COUNTY REMONUMENTATION CORNER

MAR 27 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Chippewa Located In: Corner Code #
(County)

1. Public Land Survey T46N R2W I-7
T R
T R
T R

2. Property Controlling in Section S T R
S T R

3. Miscellaneous Property in Sec. S T R
S T R

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
29 FEB 96 9:32 A.M. RECEIPT# 462
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Larry R. Rogers, in a field survey on Oct. 10, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | | | | | 3 | 2 | 1 | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | | | | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | | | | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

(I-7) Southeast Corner of Section 15, T46N, R2W

1849: Harvey Mellen "set Tamarack post at Corner" with the following witnesses:
6" Tamarack S23E 23 links 8" Spruce N29W 40 links

1988: Neil E. Hill, P.S. 27447, found 1 3/4" diameter brass cap on rod, 1.7 feet below surface in monument box, 11.2 feet North of centerline of M-28 as referenced in 1941 Highway Plans (S-11-A-1) and recorded in Liber 7, Page 84 of the Chippewa County Corner Records with the following witnesses: P. Pole S40°E 78.41'
Guy Pole N40°E 80.10' Chis. "X" SE Cor. Hdwl. W'ly end culvert S25°W 57.10'
Chis. "X" NE Cor. Hdwl. W'ly end culvert N12°W 61.06'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I-7) This corner is being perpetuated as part of Chippewa County Remonumentation program.

Found no evidence of original corner position. Found 1/2" iron in monument box (No brass cap) 11.2 feet North of the centerline of State Highway M-28. Recovered two witnesses from previous recording. Accepted corner position as found and established two new witnesses.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I-7) Corner is 1/2" iron pin in monument box 11.2 feet North of centerline of State Highway M-28.

Witnesses: Guy Pole N45°E 79.97'
Top center of square Conc. R.O.W. Marker N25°W 71.81'
Utility Pole (DR4/111) S39°E 78.43'
"X" in West end of C.M.P. S24°W 55.87'

Signed by _____
Surveyor's Michigan License No. 29251

Date 30 DEC 1995



NOTE: Bearings are compass bearings corrected for declination. Distances are to a nail in side of witness objects unless noted. FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JANUARY 1975 REVISED JAN., 1983 REVISED OCT., 1985