

CHIPPEWA COUNTY REMONUMENTATION CORNER

MAR 27 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T46N R 2W</u>	<u>T-8</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

\$ 7.00 LAND CORNER  
\$ 2.00 MSSR  
29 FEB 96 9:33 A.M. RECEIPT# 462  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

William L. Karr, in a field survey on Nov. 6, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
(I-8) 1/4 Corner common to Sections 22 and 23, T46N, R2W

1849: Mellen, D.S. set Tamarack Post for corner  
Tamarack 6" S23°E 23 links Spruce 8" N29°W 40 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
(I-8) This corner is being perpetuated as part of the Chippewa County Remonumentation program.

Found no evidence of original corner. Did find remains of an old fence to the West. Re-established corner on line between section corners to the North and South and on ext. of old fence line to West

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
(I-8) Corner is a 3/4" x 24" rerod with plastic "Chippewa County Remonumentation" cap. Corner falls 2.0 feet West of centerline of Midway Road.

Witnesses:	Power Pole	N32°E	131.89'
	6" Balsam	N69°E	137.44'
	3" Spruce	S66°W	70.59'
	NW Cor. Section 22	N03°E	2633.53'
	SW Cor. Section 22	S03°W	2621.82'



Signed by William L. Karr  
Surveyor's Michigan License No. 27450

Date 12/13/95

NOTE: Bearings are compass bearings corrected FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
for declination. Distances are to a nail in side of witness objects unless noted. REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1985