

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner \$7.00 LAND CORNER

SECTION

For corners in

Chippewa

Located In:

Corner Code #

1. Public Land Survey

T 46N R 2W

J-3

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

\$2.00 MSSR

12 Mar 1998 12:55:40 PM Receipt #6527

RECEIVED FOR RECORD

CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 241

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 1, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3										●			
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J-3) 1/4 Corner Common to Sections 2 and 11, T.46 N., R.2 W.  
1849 Harvey Mellen set Cedar post in original survey.

Witnesses: Cedar 8 S38°E 11  
Y. Birch 10 N33°W 6

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J-3) 1/4 Corner Common to Sections 2 and 11, T.46 N., R.2 W.  
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of the original corner or subsequent restoration. Reestablished the corner by single proportionate measurement (mid-way and on-line) between Section corner 1, 2, 11 and 12 and Section corner 2, 3, 10 and 11. Distance East and West is 2637.55' (GLO-2639.34').

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J-3) 1/4 Corner Common to Sections 2 and 11, T.46 N., R.2 W.  
Corner is a 3/4" x 48" iron with stamped aluminum Chippewa County Remonumentation Corner cap, 6" above grade. Placed a steel fence post 1.0' North of corner.

Witnesses: Balsam 6" N17°8E 13.82'  
Balsam 8" S46°E 45.60'  
Balsam 12" S44°W 19.41'  
Spruce 14" N32°W 45.37'

Signed by William L. Karr

Date 12/24/97

Surveyor's Michigan License No. 27450

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.

