

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE SECTION
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner \$7.00 LAND CORNER

For corners in

Chippewa

Located In:

Corner Code #

1. Public Land Survey

T 46N R 2W

J-11

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

12 Mar 1998 12:58:48 PM Receipt #6527
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEY, REGISTER OF DEEDS
BOOK 10 PAGE 243

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on November 25, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid showing sections 1-36 with handwritten 'T 46N R 2W' and a dot in section 26.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J-11) 1/4 Corner Common to Sections 26 and 35, T.46 N., R.2 W.
1849 Harvey Mellen set Cedar post in original survey.

Witnesses:

Cedar 6
B. Ash 8

N40°E 23
S52°W 54

??? County Surveyor Section Drawing Book indicates the East 1/2 mile as 2643' and Ino Murphy corner at the 1/4 corner. No mention of overall distance or West 1/2 mile.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J-11) 1/4 Corner Common to Sections 26 and 35, T.46 N., R.2 W.
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of the original corner or subsequent restoration. Found a fence line to the North in the area of 1/4 corner. Reestablished the corner on line between adjacent Section Corners and on the extension of the fence line to the North. Distance East is 2639.95'; distance West is 2633.95'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J-11) 1/4 Corner Common to Sections 26 and 35, T.46 N., R.2 W.

Corner is a 3/4" x 24" iron with plastic Chippewa County Remonumentation Corner cap, 3'± South of the centerline of unimproved 11 Mile road (East-West) and on the extension of an old fenceline to the North.

Witnesses: Fence post N21°E 25.78'
Post S05°E 13.63'
3/4" I.D. capped witness pipe S63°W 56.03'
3/4" I.D. capped witness pipe N55°W 56.60'

Signed by William L. Karr

Date 12/25/97

Surveyor's Michigan License No. 27450

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

