

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

SECTION

For comers in

Chippewa Located In: Corner Code #
1. Public Land Survey T 46N R 2W K-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

\$7.00 LAND CORNER
\$2.00 NSSR
12 Mar 1998 12:59:29 PM Receipt #6527
RECEIVED FOR RECORD
CHIPPWEA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS
BOOK 10 PAGE 244

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

I, William L. Karr, in a field survey on November 25, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Includes handwritten annotations 'T 46N R 2W' and 'R 2W'.

A. Description of original monument and accessories and/or subsequent restoration:

(K-8) 1/4 Corner Common to Sections 23 and 24, T.46 N., R.2 W.
1849 Harvey Mellen set Tamarack post in original survey.

Witnesses: Maple 12 S64°E 18
W. Pine 15 N38°W 42

Found no record of subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-8) 1/4 Corner Common to Sections 23 and 24, T.46 N., R.2 W.
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of the original corner or subsequent restoration. Found a large cedar post at a fence interseccion (East, South and West). Reestablished corner at base of large post. Distance to the North and South is 2638.47'. Corner falls 4.10' West of a straight line between Section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-8) 1/4 Corner Common to Sections 23 and 24, T.46 N., R.2 W.
Corner is a 3/4" x 24" iron with stamped aluminum Chippewa County Remonumentation Corner cap at the intersection of an East-West electric fence and fence line to the South.

Witnesses: 3/4" I.D. capped pipe N76°E 68.07'
First post South of corner South 87.90'
First post West of corner West 93.61'
3/4" I.D. capped pipe North 53.94'

Signed by [Signature]

Date 12/29/97

Surveyor's Michigan License No. 27450

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.

