

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

SECTION

For corners in

Chippewa	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>2W</u>	<u>K-9</u>
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

\$7.00 LAND CORNER
\$2.00 MSSR
12 Mar 1998 1:00:33 PM Receipt #6527
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS
BOOK 10 PAGE 245
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William L. Karr, in a field survey on November 25, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K-9) Section Corner Common to Sections 23, 24, 25 and 26, T.46 N., R.2 W.

1849 Harvey Mellen set B. Ash post in original survey. Witnesses: B. Ash 6 S61°E 31
B. Ash 12 N30°W 3 1/2

??? County Surveyor Corner tie book shows a cement monument and cedar post along with several witnesses.

1987 K. Waters, PS. 28424 found an old concrete monument and set a 1/2" x 18" iron and cap at road surface.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-9) Section Corner Common to Sections 23, 24, 25 and 26, T.46 N., R.2 W.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of the original corner. Found 1/2" iron as set by Waters. Cap was destroyed. Accepted corner as found and established (1) new witness.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-9) Section Corner Common to Sections 23, 24, 25 and 26, T.46 N., R.2 W.

Corner is a 1/2" iron with destroyed yellow plastic cap, 4" below grade on the centerline of a road to the South and 1.5' North of centerline of an East-West road.

Witnesses: P. Pole (DR1/111/31) S30°E 60.87' (existing tag)
Magnail South end of Culvert S66°W 44.76'
Burr Oak 23" N54°W 99.67' (existing tag)
Ash 10" N16°W 53.70' (existing tag)

Signed by William L. Karr Date 12/29/97

Surveyor's Michigan License No. 27450

NOTE: All bearings are compass bearings corrected for declination (6° W). All distances are to a nail and tag in the side of witness object unless otherwise noted.

