

APR 07 1998

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 Chippewa County Remonumentation Corner

**SECTION**

For corners in

Chippewa Located In: Corner Code #

1. Public Land Survey T 46N R 2W K-10  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_  
 T \_\_\_ R \_\_\_

2. Property Controlling in Section S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_  
 S \_\_\_ T \_\_\_ R \_\_\_

\$7.00 LAND CORNER  
 \$2.00 MSSR  
 12 Mar 1998 1:00:59 PM Receipt #6527  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS  
 BOOK 10 PAGE 246

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, William L. Karr, in a field survey on November 25, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7				9		10		11		12	
5													
6		18		17				15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K-10) 1/4 Corner Common to Sections 25 and 26, T.46 N., R.2 W.  
 1849 Harvey Mellen set Cedar post in original survey. Witnesses: Y. Birch 16 S17°W 11  
 Maple 12 N89°E 13

1900 and 1912 F.H. Brown, County Surveyor ran the West line of Section 25. Overall distance was 5282. There was no mention of the 1/4 corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-10) 1/4 Corner Common to Sections 25 and 26, T.46 N., R.2 W.  
 This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of the original corner. Found a 1/2" iron in the centerline of Kinross Road and on the extension of an old fence line to the East. Corner is 4.10' West a straight line between adjacent Section corners. Distance North is 2641.23'; distance South is 2639.21'. Accepted corner position as found and established (2) new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-10) 1/4 Corner Common to Sections 25 and 26, T.46 N., R.2 W.  
 Corner is a 1/2" iron 2" below grade in the centerline of Kinross road on the extension of an old fence to the East.

Witnesses: Power pole N51°E 40.03' (existing tag)  
 Steel post S18°W 66.70'  
 Power pole N87°W 37.54'  
 Aspen 6" N37°W 37.54' (existing tag)

Signed by William L. Karr Date 12/25/97

Surveyor's Michigan License No. 27450

NOTE: All bearings are compass bearings corrected for declination (6°W). All distances are to a nail and tag in the side of witness object unless otherwise noted.

