

DAFTER TWP

# SURVEY & REMONUMENTATION

APR 07 1998

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 Chippewa County Remonumentation Corner

For corners in

SECTION

Chippewa

Located In:

Corner Code #

- 1. Public Land Survey      T 46N R 2W      K-12
- T    \_\_\_ R    \_\_\_
- T    \_\_\_ R    \_\_\_
- T    \_\_\_ R    \_\_\_
- 2. Property Controlling    S    \_\_\_ T    \_\_\_ R    \_\_\_
- in Section               S    \_\_\_ T    \_\_\_ R    \_\_\_
- 3. Miscellaneous           S    \_\_\_ T    \_\_\_ R    \_\_\_
- Property in Sec.         S    \_\_\_ T    \_\_\_ R    \_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, William L. Karr, in a field survey on November 13, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

\$7.00 LAND CORNER  
 \$2.00 MSSR  
 12 Mar 1998 1:01:54 PM Receipt #6527  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS  
 BOOK 10 PAGE 248

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K-12) 1/4 Corner Common to Sections 35 and 36, T.46 N., R.2 W.  
1849 Harvey Mellen set post in original survey. Witnesses:

1893 F.H. Brown County Surveyor ran Section Line 35/36 and notes 2641' for each 1/2 mile.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-12) 1/4 Corner Common to Sections 35 and 36, T.46 N., R.2 W.  
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found no evidence of the original corner or subsequent restoration. Reestablished the corner by single proportionate measurement (mid-way and on-line). Distance North and South is 2641.26' (C.S. 2641').

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-12) 1/4 Corner Common to Sections 35 and 36, T.46 N., R.2 W.

Corner is a 3/4" x 24" iron with plastic Chippewa County Remonumentation Corner cap, 6" below grade and 5'± West of the centerline of Kinross road. Corner falls on a woods line. This may be an old Right-of-Way line (no remains of a fence).

- Witnesses:
- 3/4" I.D. capped witness pipe      N52°E    51.43'
  - Corner Fence Post                    S75°E    32.19'
  - White Pine 18"                        S45°W    46.73'
  - 3/4" I.D. capped witness pipe      N45°W    55.62'

NOTE: The witness pipes are 3/4" x 24" pipes with pipe caps set 1' below grade. The angle between the pipes is 96°37'19".

Signed by William L. Karr

Date 12/21/97

Surveyor's Michigan License No. 27450

NOTE: All bearings are compass bearings corrected for declination (6"W). All distances are to a nail and tag in the side of witness object unless otherwise noted.

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1975

