

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

Two Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 2 W.	G-2 7- <u>Sec. 4</u>
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 7/15 1971, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-2 $\frac{1}{4}$ Corner bet. Secs. 3-4, set during original survey of township, July 16, 1849.
Bearings were: hem. 10" S80°W 18 LKS. and hem. 14" S20°E 15 LKS.
- 7-Sec. 4 North 1/16 corner, on eastside, Section 4.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-2 Found a 4" concrete monument with 1" iron, set by C. H. Cade, P. E., August 1930. Location agrees with other monuments identified on Cades' map.
- 7-Sec. 4 Found a 4" concrete monument with 1" iron, set by C. H. Cade, P. E., August 1930, while making a boundary survey of Brimley State Park.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-2 Re-Witnessed Corner
New Bearings: 9" W. Birch N65°W 30.3' and 12" W. Birch S20°W 32.2'
- 7-Sec. 4 Re-Witnessed Corner
New Bearings: 9" Cedar S27°E 35.6' and 7" Tamarack N75°E 10.5'

SIGNED BY Billy D. Buckler DATE 12/15/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____