

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
 Chippewa

(County)

Located In:

Corner Code //

1	Public Land Survey	T	46N	R	2W	C-11
		T		R		
		T		R		
		T		R		
2.	Property Controlling	S		T		
	in Section	S		T		
3.	Miscellaneous	S		T		
	Property in Sec.	S		T		

Register of Deeds Stamp & File Number

4 Lot No. . . . . Recorded Plat \_\_\_\_\_  
 5 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	13	17	15	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gerald L. Wiggins, in a field survey on 3-15, 19 90  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
 on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-11 Section Corner Common to Sections 30-29-31-32. Found a buried 1/2" Iron in road set by  
 unknow surveyor.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 Placed corner at found 1/2" Iron set by unknown surveyor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 1" Pipe with plastic RLS Cap buried in road.

14" Spruce, S70°W, 49.2'  
 12" Twin W. Birch, N45°W, 66.7'  
 12" Aspen, N72°E, 35.0'  
 6" Aspen, S44°E, 47.1'


Signed by

*Gerald L. Wiggins*

Date 9-13-90

Surveyor's Michigan License No

23521



FORM APPROVED BY MICHIGAN

LAND SURVEYORS, JAN. 20, 1951  
 REVISED MAY 14, 1976  
 REVISED JAN., 1983