

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CHIPPEWA

(County)

Located In:

Corner Code #

- | | | | | | | |
|------------------------------------|---|---|-----|---|----|------|
| 1. Public Land Survey | | T | 46N | R | 2W | C-12 |
| | | T | | R | | |
| | | T | | R | | |
| | | T | | R | | |
| 2. Property Controlling in Section | S | T | | R | | |
| | S | T | | R | | |
| 3. Miscellaneous Property in Sec | S | T | | R | | |
| | S | T | | R | | |

Register of Deeds Stamp & File Number

4. Lot No _____, Recorded Plat _____
 5. Private Claims _____

I, Gerald L. Wiggins, in a field survey on 10-29, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-12 1/4 between sections 31 and 32. Set during the original land survey of Michigan.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-12 Corner set midpoint on line between the N.W. Corner and S.W. Corner of Section 32.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-12 1" pipe with plastic RLS Cap. 16" Tamarack, S47°W, 130.1'
 8" Tamarack, S21°W, 212.1'
 Sec. Cor., South, 2635.29'
 Sec. Cor., North, 2635.29'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by

Gerald L. Wiggins
 Gerald L. Wiggins

Date 6-26-91

Surveyor's Michigan License No.

23521

FORM APPROVED BY MICHIGAN STATE

