

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Chippewa County Remonumentation Corner**

SECTION

For corners in

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T46N R7W	G-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

BOOK **11** PAGE **102**

\$7.00 LAND CORNER  
 \$2.00 MSSR  
 23 FEB 2000 4:25:02 PM Receipt #21179  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on November 23, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-11 Corner Common to Sections 27, 28, 33, & 34, T46N, R7W

1850 - Original corner established by Wells Burt, a tamarack post.  
 Witnesses: Tamarack 8, S70°W 11 links - Tamarack 9, S30°E 19 links.

Found no evidence of subsequent restoration of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found a "T" iron next to a square wood post, with three blazed trees facing the found corner. Accepted found "T" iron as best available evidence of the corner location. Replaced the "T" iron with a 3/4" x 24" rebar and a stamped aluminum Chippewa County Remonumentation cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced a found "T" iron with a 3/4" x 24" rebar and a stamped aluminum Chippewa County Remonumentation cap at the corner location, next to a found square wood post. Corner falls approximately 100 feet north of the old Soo Line Railroad Grade.

- Witnesses:
- Nail and tag #33142 in blazed 10" Tamarack, N61°W 19.33' (existing bearing tree)
  - Nail and tag #33142 in blazed 3" Balsam Fir, N82°W 7.35' (existing bearing tree)
  - Nail and tag #33142 in blazed 10" Spruce, S10°W 9.81' (existing bearing tree)
  - Nail and tag #33142 in blazed 4" Spruce, N42°E 10.07' (new bearing tree)



Signed by Keith R. Waters

Date 12-29-99

Surveyor's Michigan License No. 33142