

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

For corners in

Table with columns: Chippewa County, Located in:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

BOOK 11 PAGE 116

\$7.00 LAND CORNER
\$2.00 HSSR
23 FEB 2000 4:37:15 PM Receipt #Z1179
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column K and row 9.

I, Keith R. Waters, in a field survey on November 9, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-9 Corner Common to Sections 23, 24, 25, & 26, T46N, R7W

1850 - Original corner established by Wells Burt, a cedar post.
Witnesses: Spruce 10, S22°E 22 links - Cedar 12, N53°W 22 links.

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being reestablished as part of the Chippewa County Remonumentation Program. Found no evidence of the original corner. Reestablished corner by double proportionate measurement, using the section corner on the range line at M-9 to the east, the section corner at I-9 to the west, the section corner at K-11 to the south, and the south bank of the Tahquamenon River to the north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 3/4" x 24" rebar with a stamped aluminum Chippewa County Remonumentation cap at the corner location.

- Witnesses:
Nail and tag #33142 in 7" blazed Cedar, S33°W 51.70'
Nail and tag #33142 in 14" blazed Tamarack, N41°W 9.86'
Nail and tag #33142 in 12" blazed Spruce, N38°E 18.97'
Nail and tag #33142 in 11" blazed Cedar, S62°E 42.30'



Signed by Keith R. Waters

Date 12-29-99

Surveyor's Michigan License No. 33142