

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
 Chippewa County Remonumentation Corner

BOOK **11** PAGE **118**

For corners in SECTION

| | | |
|------------------------------------|-------------|---------------|
| Chippewa County | Located in: | Corner Code # |
| 1. Public Land Survey | T46N R7W | K-11 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. , Recorded Plat | | |
| 5. Private Claims | | |

\$7.00 LAND CORNER
\$2.00 MSSR
 23 FEB 2000 4:38:35 PM Receipt #21179
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on June 30, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

K-11 Corner Common to Sections 25, 26, 35, & 36, T46N, R7W


1850 – Original corner established by Wells Burt, a beech post.
 Witnesses: Beech 10, N54°E 08 links – Beech 12, S70°W 25 links.

1917 – Chippewa County Surveyor's notes indicate an original corner at this location, 2650 feet north of an original ¼ corner at K-12 to the south. Witnesses: Hemlock 12, Northeast 40' – Birch 10, S10°E 28'.

1922 – Chippewa County Surveyor's notes again indicate an original corner, bearing trees standing.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being reestablished as part of the Chippewa County Remonumentation Program. Found no evidence of the original corner or the subsequent bearing trees as shown in the above mentioned 1917 County Surveyor notes. Reestablished corner at record County Surveyor distance (2650 feet) north of the ¼ corner at K-12, at the proportionate east-west GLO distance between the section corner at M-11 on the range line to the east and the ¼ corner at J-11 to the west. This total east-west distance is within 8 feet of the record GLO distance in 1½ miles.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a ¼" x 24" rebar with a stamped aluminum Chippewa County Remonumentation cap at the corner location.
 Witnesses:

- Nail and tag #33142 in 9" blazed Sugar Maple, N16°E 19.85'
- Nail and tag #33142 in 10" blazed Sugar Maple, S64°E 6.30'
- Nail and tag #33142 in 14" blazed Sugar Maple, S66°W 26.04'
- Nail and tag #33142 in 9" blazed Sugar Maple, N26°W 26.97'



Signed by Keith R. Waters

Date 12-29-99

Surveyor's Michigan License No. 33142