

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

For corners in SECTION

BOOK **11** PAGE **121**

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T46N R7W	L-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$7.00 LAND CORNER
 \$2.00 MSSR
 23 FEB 2000 4:40:48 PM Receipt #2117
 RECEIVED FOR RECORD
 CHIPPEWA COUNTY - STATE OF MICHIGAN
 SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
 5. Private Claims

I, Keith R. Waters, in a field survey on November 9, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-9 1/4 Corner Common to Sections 24 & 25, T46N, R7W

1850 - Original corner established by Wells Burt, a spruce post.
 Witnesses: Tamarack 10, S51°E 10 links - Tamarack 5, N07°W 18 links.

Found no evidence of subsequent restoration of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being reestablished as part of the Chippewa County Remonumentation Program.
 Found no evidence of the original corner. Reestablished corner by single proportionate measurement midway on line between the section corner at M-9 on the range line to the east and the section corner at K-9 to the west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 3/4" x 24" rebar with a stamped aluminum Chippewa County Remonumentation cap at the corner location.

- Witnesses:
 Nail and tag #33142 in 4" blazed White Birch, S88°W 29.33'
 Nail and tag #33142 in 14" blazed Cedar, S45°W 20.61'
 Nail and tag #33142 in 10" blazed Cedar, S11°E 23.91'
 Nail and tag #33142 in 8" blazed Cedar, N27°W 10.26'



Signed by Keith R. Waters

Date 12-29-99

Surveyor's Michigan License No. 33142