

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Chippewa County Remonumentation Corner**

For corners in SECTION

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T46N R7W	L-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

BOOK **11** PAGE **122**

\$7.00 LAND CORNER  
 \$2.00 MSSR  
 23 FEB 2000 4:41:23 PM Receipt #21179  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on June 30, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-11 1/4 Corner Common to Sections 25 & 36, T46N, R7W

1850 – Original corner established by Wells Burt, a 6" spruce.  
 Witness: Cedar 12, N40°W 04 links.

1917 – Chippewa County Surveyor's notes indicate "could not find 1/4 post and divided up equally."  
 Witnesses: Yellow Birch 30, S65°E 15 – Yellow Birch 18, N65°W 43 1/2.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being reestablished as part of the Chippewa County Remonumentation Program. Found no evidence of the original corner or the corner as reestablished in 1917. Reestablished corner by single proportionate measurement midway on line between section corners at K-11 and M-11.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 3/4" x 24" rebar with a stamped aluminum Chippewa County Remonumentation cap at the corner location.  
 Witnesses:  
 Nail and tag #33142 in 12" blazed Cedar, N12°E 23.10'  
 Nail and tag #33142 in 10" blazed White Birch, S84°E 15.08'  
 Nail and tag #33142 in 16" blazed Cedar, S53°W 13.38'  
 Nail and tag #33142 in 14" blazed Cedar, N80°W 15.23'

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												



Signed by Keith R. Waters

Date 12-29-99

Surveyor's Michigan License No. 33142