

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippew

	Located In:	Corner Code //
1 Public Land Survey	T 46N R 7W	I-12
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2 Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3 Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4 Lot No	Recorded Plat _____	
5 Private Claims	_____	

Register of Deeds Stamp & File Number

I, Gerald L. Wiggins, in a field survey on 5-4 1990
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law, established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-12 1/4 Corner between Sections 34-35 set by Wells Burt in 1850. DBT'S: W. Pine 10", S74°E,
20 links and W. Pine 12", S26°W, 22 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12 Corner set at a very old wood stake and two original B.T.'S. a W. Pine 10", S74°E, 20 links
still living and is now a 24", a W. Pine Stump, S26°W, 22 links.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 DNR Monument: 12" Cedar, S31°E, 20.05'
6" Cedar, S68°W, 9.30'
8" Cedar, N20°W, 6.90'
24" W. Pine, S74°E, 13.20'

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4													
5													
6													
7													
8	16	17	18	19	20	21	22	23	24	25	26	27	28
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	46	47	48	49	50	51	52	53	54	55	56	57	58
13													

Signed by Gerald L. Wiggins Date 9-13-90
Surveyor's Michigan License No. 23521

