

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Chippewa  
(County)

Located In: Corner Code #  
T 46N R 1W M-4 Same  
T 46N R 1E A-4 Corner  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

94 JUL 22 AM 11:10

*J. Roger Matlock*

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey \_\_\_\_\_
- 2. Property Controlling \_\_\_\_\_  
in Section \_\_\_\_\_
- 3. Miscellaneous \_\_\_\_\_  
Property in Sec. \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Keith R. Waters, in a field survey on SEPTEMBER 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
(M-4) East 1/2 Corner of Section 12 (T46N-R1W)

Original GLO Notes, August 27, 1840, Set 1/2 Section Post  
B. Ash 4" S13W 12  
Birch 8" N47W 13

1985: L.R. Rogers re-established corner (Liber 6, Page 290).  
Corner Fence Post West 12.40'  
Fence Post N16°W 40.03'  
8" Aspen (Scribed) N18°E 53.78'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-4) Found corner and accessories as recorded in Liber 6, Page 290 of the Chippewa County Records. Accepted corner position as found.

SURVEY &  
REMONUMENTATION

JUL 26 1994

COMMISSION



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-4) Corner is a 1/2" x 18" iron with L.S. cap #29251 West of fence post.

Witnesses:

Corner Fence Post West 12.40'  
Fence Post N16°W 40.03'  
8" Aspen (Scribed) N18°E 53.78'

Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 7-22-94

483-00

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted