

1993

CHIPPEWA COUNTY REMONUMENTATION CORNER

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC -3 PM 3:58

For corners in
Chippewa

(County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 1E T 46N R 1W	A-6 Same Corner
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on October 28, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-6 (T46N, R1E)
1/4 Corner Common to Section 18, T46N, R1E & Section 13, T46N, R1W

Original ties to set post (Wm. A. Burt, D.S., 1840):

- Fir 8, S49°W 29 links
- Fir 6, N73°W 16 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 (T46N, R1E)
This corner is being re-established as part of the Chippewa County Remonumentation Program.
Found no evidence of corner or its accessories. Re-established corner on line between Section corners 1/2 mile north and 1/2 mile south at the intersection of an old fence line to the east. North-south position fits well with an east-west fence line at the North 1/16 line of Section 13, T46N, R1E. Corner measures 2604.50 feet to Section corner north and 2696.75 to Section corner south, and is approximately 1 foot west of a north-south fence line. Considerable difference between distances to Section corners north and south is consistent with distances as shown in County Surveyor notes dating back to 1906.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 (T46N, R1E)
Corner is a 3/4" x 24" rebar with a 3 1/2" Chippewa County Remonumentation cap approximately 1' west of a north-south fence line at a fence line to the east.
Witnesses:

- Fence Post, EAST 1.17'
- 3" Spruce, N31°E 53.08'
- 4" Spruce, N61°E 65.30'
- 4" Spruce, S43°E 70.89'

Note: Distances are to a nail and tag in the side of witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.

Signed by Keith R. Waters Date 11-30-93
Surveyor's Michigan License No. 33142

