

SURVEY &
REMONUMENTATION

1993

COMMISSION

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 NOV 31 AM 9:55

J. Roger Malott
REGISTER OF DEEDS

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T 46N R 1E	<u>B-1</u> Same
	T 47N R 1E	<u>B-13</u> Corner
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William L. Karr, in a field survey on May 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(B-1/B-13) 1/4 Corner Sections 6 & 31, T46N-R1E/T47N-R1E)

1989 William L. Karr, L.S. 27450
Recorded in Liber 7, Page 320 of Corner Records (recorded as Common)
Found a 1 1/4" O.D. pipe in a monument box.
Power Pole DR3/112 N53°E 84.57'
Corner Fence Post S67°E 62.16'
Power Pole DR3/111 N49°W 87.76'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B-1/B-13) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Corner was previously recorded as common, and used as a common corner through the years. Found corner as recorded. Found all three record ties. Discovered a 1' discrepancy in one of the ties. Added one additional tie. Accepted corner as found.

D. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B-1/B-13) Corner is a 1 1/4" O.D. pipe in a monument box. Falls on centerline of Six Mile Road and 12' West of centerline of M-129.

Witnesses: Power Pole DR3/112 N53°E 83.57'
Corner Fence Post S67°E 62.20'
Power Pole DR3/111 N49°W 87.76'
Concrete right-of-way post (punchmark in top) S51°W 69.22'



Signed by William L. Karr Date 11/12/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.