

SURVEY & REMONUMENTATION

1993

COMMISSION

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 NOV 31 AM 9:55

J. Roger Malott
REGISTER OF DEEDS

For corners in

Chippewa

(County)

Located In:

Corner Code =#

1. Public Land Survey	T 46N	R 1E	C-1
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, William L. Karr, in a field survey on May 20, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C-1) Closing Corner Sections 5 & 6, T46N-R1E

1989 William L. Karr, L.S. 27450
Recorded in Liber 7, Page 318 of Corner Records.
Set 1/2" iron L.S. 27450

Wood Corner Fence Post	N60°E	45.39'
Power Pole DR/112/8N	S54°E	50.20'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-1) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found corner and ties as recorded.
Added two additional ties.
Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C-1) Corner is a 1/2" iron L.S. 27450, and falls in the West ditch of Killackey Road, 13' West of centerline.

Witnesses: Wood Corner Fence Post (Leaning East)	N60°E	45.76'
Power Pole DR1/112/8N (Nail on North side)	S54°E	50.22'
Wood Corner Fence Post	N70°W	17.12'
1/2" iron L.S. 33142 (Standard corner)	East	31.58'



igned by William L. Karr Date 11/12/93

urveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.