

MAY 28 1997

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner \$7.00 LAND CORNER

For corners in

Chippewa County	Located in	n:	Corner Code #
1. Public Land Survey	ן ז ד	46N R1E R R	C-12
	S 1 S 1 S 1 S 1	R R R R	

\$2.00 MSSR 2/28/1997 3:12:41 PK Receipt #217 RECEIVED FOR RECORD CHIPPENA COUNTY - STATE OF MICHIGAN SHARON H. KEHNEDY, REGISTER OF DEEDE

BOOK 9 PAGE 375

10

Register of Deeds Stamp & File Number


4. Lot No.

, Recorded Plat

Private Claims

I, William L. Karr, in a field survey on October 15, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



(C-12) 1/4 Corner Common to Sections 31 & 32, T. 46 N., R. 1 E.

1845 J.H. Mullett in Original Survey, 10" Maple for 1/4 Section Post.

F.H. Brown in records in County Surveyors Office show that no evidence of the Original Corner was found and the mile was divided up evenly, 1467.5 x 4.

1918 F.H. Brown in records in County Surveyors Office again show the mile evenly divided as in 1898.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C-12) 1/4 Corner Common to Sections 31 & 32, T. 46 N., R. 1 E. This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found 1/2" iron with cap set by R. Bischer, PS 22428, at the intersection of old and well established fence lines North, Found 1/2" iron with cap set by K. Bischer, Po 22420, at the intersection of the state of the state of being and income south and West, and an old fallen down fence to the East. Bischer's corner falls 1' North and 3' West of being and income. and an even division of the mile.

Accepted Bischer's iron for the 1/4 corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

(C-12) 1/4 Corner Common to Sections 31 & 32, T. 46 N., R. 1 E.

Corner is a 1/2" iron with plastic cap no. 22428 set on the South side of a fence post at the intersection of fences North, South, East and West.

Witnesses:

10" Aspen N 50° E Fence Post S 84° E 8.50' 8" Maple N 80° W 56.45 15" White Birch N 34° W 37.46

KARR LAND JRVEY**OR** 

Bearings are compass bearings, corrected for declination, all distances are to a nail with a Bischer Survey witness objects.

Signed by

Date 12-30-4

Surveyor's Michigan License No. 27450