

**SURVEY & REMONUMENTATION CHIPPEWA COUNTY REMONUMENTATION CORNER CHIPPEWA COUNTY STATE OF MICHIGAN**

MAR 09 1994

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 30 PM 2:42

For corners in  
**Chippewa**  
(County)

**COMMISSION**

Located In:

Corner Code #

*J. Roger Martelle*  
REGISTER OF DEEDS

- |                                    |                          |             |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey              | T <u>46N</u> R <u>1E</u> | <u>C-13</u> |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
|                                    | T _____ R _____          | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____       |
|                                    | S _____ T _____ R _____  | _____       |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on December 2, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

C-13 Corner Common to Sections 31 & 32, on South Boundary of T46N, R1E  
(Standard Corner on Township Line)

Original ties to post: Fir 10, N60°E 26 links  
Birch 8, N81°W 14 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 (T46N, R1E)

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a PK nail 1.8 feet north of the centerline of 12 Mile Road road, on the extension of a fence line on the north side of road. Also found a 1/2" iron with cap #29251 at the closing corner 15.18 feet east. Record GLO falling is 23 links (15.18 feet). Location also matches old County Surveyor notes. Accepted corner location as found. Replaced PK nail with a 3/4" rebar and plastic Chippewa County Remonumentation cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 (T46N, R1E)

Corner is a 3/4" rebar with a plastic Chippewa County Remonumentation cap 1.8 feet north of the centerline of east-west asphalt road (12 Mile Road) at a fence line to the north. Witnesses:

- 6" Spruce, S22°W 150.86'
- Power Pole (DR2-91-14), S34°E 67.68'
- Telephone Pole (M-73), N78°E 157.12'
- Corner Fence Post, N05°E 49.95'
- 1/2" Iron w/cap #29251, EAST 15.18'
- (Closing Cor. Secs. 5-6, T45N, R1E)

Note: Distances are to a nail and tag in the side of witness object. Spruce is blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-30-93

Surveyor's Michigan License No. 33142