

SURVEY & REMONUMENTATION

CHIPPEWA COUNTY REMONUMENTATION CORNER RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

MAR 09 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 30 PM 2:43

COMMISSION

For corners in
Chippewa
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>46N</u> R <u>1E</u> | <u>D-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

J. Roger Matlock
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on December 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13 South 1/4 Corner of Section 32, T46N, R1E

Original corner was a 8" Balsam Fir.

1983 - This corner is shown on a drawing by Larry R. Rogers, P.S. 29251, of Northwoods, Inc., as being 2630.18 feet east of standard corner at the southwest corner of Section 32, T46N, R1E, and 3.37 feet west of the north 1/4 corner of Section 5, T45N, R1E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 (T46N, R1E)

This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found no evidence of corner. Re-established corner mid-way on line between standard corners on Township line 2630.20 feet east and 2630.20 feet west. Position fits within 0.02 feet of that as shown on above mentioned drawing. Found a PK nail 3.46 feet east at the north 1/4 corner of Section 5, T45N, R1E. (Replaced PK nail with a 3/4" rebar and plastic Chippewa County Remonumentation cap).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 (T46N, R1E)

Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap 1 foot north of the centerline of east-west asphalt road (12 Mile Road).

