

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

For corners in

Table with columns: Chippewa County, Located in:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

\$7.00 LAND CORNER

\$2.00 MSSR

2/28/1997 3:11:16 PM Receipt #217
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 373

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on August 28, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-8) 1/4 Corner Common to Sections 20 & 21, T. 46 N., R. 1 E.

1845 J.H. Mullett set post in original survey.

1984 W.L. Karr PS 27450 found 5/8" iron 4' west of centerline gravel road and recorded as corner in Liber 6, Page 132 Chippewa County Corner Records.

1992 L.R. Rogers PS 29251, in a survey in section 21, Northwoods Land Surveying job number 419-37, found iron as recorded by Karr in 1984 3.5' below road surface. Raised corner to surface with a 1/2" x 48" re-bar with cap no. 29251.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-8) 1/4 Corner Common to Sections 20 & 21, T. 46 N., R. 1 E.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found corner as recorded by Karr in 1984 and raised to surface by Rogers in 1992. Accepted corner position as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-8) 1/4 Corner Common to Sections 20 & 21, T. 46 N., R. 1 E.

Corner is a 1/2" x 48" re-bar with plastic cap no. 29251, 4.5' West of centerline of Shunk Rd. (gravel). Corner is 0.3' below grade.

Table with columns: Witnesses, Bearing, Distance. Rows include 7th Fence Post North of Corner, Fence Post, Corner Fence Post, 8th Fence Post North of Corner.

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by William L. Karr

Date 12-30-96

Surveyor's Michigan License No. 27450

