

SURVEY & REMONUMENTATION

CHIPPEWA COUNTY REMONUMENTATION CORNER

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

MAR 09 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 30 PM 2:43

For corners in Chippewa **COMMISSION**

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>1E</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on December 16, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


A. Description of original monument and accessories and/or subsequent restoration:

E-13 Corner Common to Sections 32 & 33, on South Boundary of T46N, R1E (Standard Corner on Township Line)

Original ties to post: Maple 12, N23°E 20 links Maple 16, N20°W 21 links
1980 - Corner shown on survey recorded in liber 2 of Surveys, page 166, by Thomas M. Kelly, R.L.S. 24599, as a 1" iron pipe.
1985 - Corner recorded by Larry R. Rogers, P.S. 29251, in liber 6, page 286 of Chippewa County corner records, as a 1" pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 (T46N, R1E)
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a 1" iron pipe 1.7 feet north of centerline of east-west asphalt road (12 Mile Road) at the centerline of gravel road to the north (Shunk Road) as shown on recorded survey and previous corner certificate. Accepted corner as found and established new witness objects as necessary.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 (T46N, R1E)
Corner is a 1" iron pipe 1.7 feet north of the centerline of 12 Mile Road, at the centerline of Shunk Road to the north. Witnesses:

- Power Pole (DR1-76-43), N20°W 56.10'
- 4" Spruce, S52°W 56.63'
- 12" Spruce, S32°E 96.63'
- SW Cor. Hse. Foundation, N62°E, 152.88'
- 1/2" Iron w/cap #29251, EAST 7.92'
- (Closing corner Secs. 4-5, T45N, R1E)

Note: Distance to pole and spruces is to a nail and tag in the side. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-30-93

Surveyor's Michigan License No. 33142