

**SURVEY & REMONUMENTATION**

1993

COMMISSION

Chippewa County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

93 NOV 31 AM 9:55

*J. Roger Malott*  
REGISTER OF DEEDS

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>1E</u>	<u>F-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on July 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F-1) North 1/4 Corner of Section 4, T46N-R1E

Corner not set in original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F-1) This corner is being established as part of the Chippewa County Remonumentation Program.

Corner position was established midway between the Northwest and Northeast corners of Section 4 and on a line between the Southwest corner and the South 1/4 corner of Section 33.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F-1) Corner is a 3/4" x 24" iron with stamped 2 1/2" diameter aluminum cap (Chippewa County Monumentation) P.S. 27450. Corner falls 17' more or less East of the centerline gravel drive along curve and on the extension of the centerline of a gravel drive to the South. Falls 24' more or less South of the extension of the centerline of 6 Mile Road to West.

Witnesses: 12" Aspen	N12°E	88.68'
11" Elm	N74°E	82.77'
Wood Angle fence post	N82°W	46.09'
"V" cut in North end of C.M.P.	N26°E	23.01'
South 1/4 Corner Section 33	East	22.45'

Signed by William L. Karr Date 11/12/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

