

MAR 05 1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

corners in

Chippewa
(County)

Located In:

Corner Code #

Public Land Survey

Property Controlling

In Section

Miscellaneous

Property in Sec.

Lot No. _____, Recorded Plat _____

Private Claims _____

Keith R. Waters

July 20

92

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

E-6 West 1/4 Corner Section 16

Original ties to post:

Fir 8, N 85° E 13 links
Birch 12, N 84° W 25 links

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6

Found a "PK" nail on approximate centerline of north-south asphalt road (Shunk Rd.) on line with an old fence to the east. This corner location has been used in previous surveys in the area. Replaced "PK" nail with a 1/2" iron.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6

Set 1/2" iron with cap L.S. 33142
Ties:
6" Spruce, East 61.80'
6" Spruce, N 66° E 70.65'
Corner Fence Post, S 88° W 48.93'
Fence Post, N 37° W 77.63'

F-5 North 1/4 Corner Section 16

Original ties to post:

Birch 15, S 15° E 20 links
Fir 10, N 15° E 14 links

F-5

Found a spike on line between northwest and northeast corners of Section 16 at a fence line to the south. Corner location has been used in previous surveys in the area. Replaced spike with a 1/2" iron. (Corner is approximately 2 feet north of centerline of east-west gravel road).

F-5

Set 1/2" iron with cap L.S. 33142
Ties:
Fence Post, S 65° E 60.89'
Fence Post, South 57.70'
Fence Post, N 75° W 106.27'
(Only witnesses available)

Unless noted otherwise, measurements are to a nail with i.d. tag in the side of witness object.

signed by Keith R. Waters

Date 1-27-93

Surveyor's Michigan License No. 33142

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

93 MAR -1 AM 11:23

J. Roger Madole

REGISTER OF DEEDS
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

