

**SURVEY & REMONUMENTATION**

1993

**Chippewa County Remonumentation Corner**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD  
CHIPPEWA COUNTY  
STATE OF MICHIGAN

93 NOV 31 AM 10:48

*J. Roger Malotte*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>1E</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	*S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, Larry R. Rogers, in a field survey on November 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(G-7) Section Corner Common to Sections 15,16,21 and 22, T46N-R1E.

This corner was previously recorded in 1985 by L.R. Rogers, P.S. 29251 in Liber Page 15 of the Chippewa County Corner Records, as a 1" iron pipe, 8 1/2' North of centerline of 9 Mile Road, with the following witnesses:

Power Pole (0422/32)	N34°E	55.93'
Power Pole	S34°W	83.60'
Power Pole	S45°E	88.60'
8" Maple	N42°W	56.82'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-7) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

1" iron pipe has been replaced by the Chippewa County Road Commission with a 5/8" iron pin in a monument box during reconstruction of 9 Mile Road. Position checks with one remaining witness from 1985 records (Northeast Power Pole).

Accepted corner position as found and established new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-7) Corner is a 5/8" iron pin in monument box, approximately 8' North of centerline of 9 Mile Road.

Witnesses: Utility Pole (cut off)	N34°E	55.81'
8" Spruce	N45°W	85.52'
Utility Pole	S42°E	88.79'
Fence Post (2nd Post West of Corner Post)	S41°W	77.99'

Spruce has been blazed and painted.

Signed by *Larry R. Rogers* Date 11 Nov 1993

Surveyor's Michigan License No. 29251

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.

