

**SURVEY &  
REMONUMENTATION**

MAY 28 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
Chippewa County Remonumentation Corner

For corners in

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T46N R1E	G-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

\$7.00 LAND CORNER

\$2.00 N SSR

2/28/1997 3:07:55 PM Receipt #217  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 369

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on November 6, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G-9) Section Corner Common to Sections 21, 22, 27 & 28, T. 46 N., R. 1 E.

1845 J.H. Mullett set post in original survey.

1902 F.H. Brown in records in County Surveyors Office show a post for section corner set from original bearing trees.

19?? Sketch in Corner Tie Book in County Surveyors Office shows a small monument for corner and distances to fence corners.

1992 L.R. Rogers in a survey in section 21, Northwoods Land Surveying Job 419-37, found the remains of a concrete monument and a wood post in road intersection. Set a 1/2" x 48" iron with cap no. 29251 in center of wood post. Recorded as corner L. 9, P. 118, Chippewa County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-9) Section Corner Common to Sections 21, 22, 27 & 28, T. 46 N., R. 1 E.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found the iron and cap as recorded by Rogers in 1992 and accepted for corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-9) Section Corner Common to Sections 21, 22, 27 & 28, T. 46 N., R. 1 E.

Corner is a 1/2" x 48" re-rod with plastic cap no. 29251 in center of old wood post in road intersection, roads East, West and North. Corner is 0.7' below grade.

Witnesses:			
Fence Post	N 50° E	38.62'	
Fence Post	S 41° E	35.09'	
4" Spruce	S 77° W	59.44'	
Fence Post	N 49° W	39.80'	
8" Spruce	N 37° W	29.03'	

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness objects, otherwise noted.

Signed by William L. Karr

Date 12-30-96

Surveyor's Michigan License No. 27450

BOOK 9 PAGE 369

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995

