

MAY 28 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
 Chippewa County Remonumentation Corner

2/28/1997 3:06:37 PM Receipt #217  
 RECEIVED FOR RECORD  
 CHIPPEWA COUNTY - STATE OF MICHIGAN  
 SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 367

Register of Deeds Stamp & File Number

For corners in			
Chippewa County	Located in:		Corner Code #
1. Public Land Survey	T46N R1E		G-11
	T R		
	T R		
	T R		
2. Property Controlling in Section	S T R		
	S T R		
3. Miscellaneous Property in Sec.	S T R		
	S T R		
4. Lot No. , Recorded Plat			
5. Private Claims			

I, William L. Karr, in a field survey on November 8, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G-11) Section Corner Common to Sections 27, 28, 33 & 34, T. 46 N., R. 1 E.

1845 J.H. Mullett set post in original survey.

19?? Sketch in Corner Tie Book in County Surveyors Office shows corner and distances to fence corners, sketch notes that fence corner to the Northeast has stones piled around post.

1984 W.L. Karr, PS 27450, recorded railroad spike for corner; Liber 6, Page 110, Chippewa County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-11) Section Corner Common to Sections 27, 28, 33 & 34, T. 46 N., R. 1 E.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found 1/2" iron matching witnesses as recorded by Karr in 1984. Also found remains of old post in pile of rocks to the Northeast matching old County Surveyor notes.

Accepted 1/2" iron for the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-11) Section Corner Common to Sections 27, 28, 33 & 34, T. 46 N., R. 1 E.

Corner is a 1/2" iron 2' North of centerline of 11 mile road (gravel). Corner is 0.2' below grade.

Witnesses:	3/4" Pipe set 1' below grade in stone pile at old fence corner.	N 56° E	45.30'
	Fence Post	S 43° W	86.75'
	Power Pole	S 60° W	47.84'
	Power Pole	N 30° W	38.35'

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by William L. Karr

Date 12-30-96

Surveyor's Michigan License No. 27450

BOOK 9 PAGE 367

