

1993

Chippewa County Remonumentation Corner

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

93 NOV 31 AM 10:48

J. Roger Mahette
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T	46N	R	1E	H-7
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Larry R. Rogers, in a field survey on November 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H-7) 1/4 Common to Sections 15 & 22, T46N-R1E.

This corner was previously recorded in 1985 by L.R. Rogers, P.S. 29251 in Liber Page 15 of the Chippewa County Corner Records as a 1 1/4" pipe set over a found iron pin with the following witnesses:

16" White Pine	N13°W	69.05'
6" White Pine	S09°W	60.00'
Power Pole	S18°E	54.36'
6" White Birch	N27°E	61.72'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H-7) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Corner was removed by Chippewa County Road Commission during reconstruction of 9 Mile Road and replaced with a monument box. Found 1/2" rerod in monument box with L.S. cap 27450 (W.L. Karr). Corner position checks with 3 remaining witnesses from 1985 records (6" White Pine is gone). Accepted corner as found and established new witness object.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H-7) Corner is a 1/2" rerod with L.S. cap 27450 in monument box on centerline of 9 Mile Road.

Witnesses: 18" White Pine	N13°W	69.03'
Utility Pole	S18°E	54.33'
6" White Birch	N27°E	61.72'
1/2" iron pin	S03°W	44.98'

Pine and Birch have been blazed and painted.

Signed by *Larry R. Rogers* Date 11 Nov 1993

Surveyor's Michigan License No. 29251

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.

