

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Chippewa County Remonumentation Corner

For corners in

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T46N R1E	K-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

\$7.00 LAND CORNER

\$2.00 HSSR

2/28/1997 2:59:55 PM Receipt #217

RECEIVED FOR RECORD

CHIPPWEA COUNTY - STATE OF MICHIGAN

SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 360
 Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 2, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K-9) Section Corner Common to Sections 23, 24, 25 & 26, T. 46 N., R. 1 E.

- 1845 J.H. Mullett set post in original survey.
- 1901 F.H. Brown in Section Drawing Book in County Surveyors Office shows corner as a gas pipe and large post.
- 1909 F.H. Brown in field book in County Surveyors Office for a survey in section 35 states that Carleton had set the section corner by dividing up the three miles from the NW corner of section 24, South to the township line.
- 19?? Corner Tie Book in County Surveyors Office shows the section corner and witnesses.
- 1993 W.L. Karr, PS 27450, found RR spike for corner. Noted that corner worked well with others in area. Recorded corner in Liber 8, Page 253, Chippewa County Corner Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-9) Section Corner Common to Sections 23, 24, 25 & 26, T. 46 N., R. 1 E.

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 3/4" iron with witnesses at the position recorded by Karr in 1993. Corner falls on line and at an even split of the three miles as noted by Brown in 1909. Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-9) Section Corner Common to Sections 23, 24, 25 & 26, T. 46 N., R. 1 E.

Corner is a 3/4" iron in the intersection of centerlines of roads North-South (Lower Haylake), and East-West (Northline).

Witnesses:	8" Tamarack	N 52° E	90.50'
	Power Pole (DR1/76A4/24)	N 54° E	54.70'
	16" Spruce	S 54° E	56.95'
	20" White Pine	S 16° E	130.40'
	14" Tamarack	S 41° W	73.15'

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the monument object unless otherwise noted.

Signed by William L. Karr

Date 12-30-96

Surveyor's Michigan License No. 27450

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

BOOK 9 PAGE 360

W.L. KARR

