

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner \$7.00 LAND CORNER

For corners in

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T46N R1E	K-10
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

\$2.00 HSSR
2/28/1997 2:58:37 PM Receipt #217
RECEIVED FOR RECORD
CHIPPewa COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 359

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

I, William L. Karr, in a field survey on December 2, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K-10) 1/4 Corner Common to Sections 25 & 26, T. 46 N., R. 1 E.

- 1845 J.H. Mullett set post in original survey.
- 1907 Field book in County Surveyors Office shows the distance on the East side of section 26 as 5318'.
- 1909 F.H. Brown in field book in County Surveyors Office for a survey in section 35 states that Carleton had divided up the three miles from the NW corner of section 24, South to the township line.
- 1995 W.L. Karr, PS 27450, Northwoods Land Surveying Job 163-347 shows corner positioned mid-way and on-line with the section corners to the North and South.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-10) 1/4 Corner Common to Sections 25 & 26, T. 46 N., R. 1 E.

This corner is being reestablished as part of the Chippewa County Remonumentation Program.

Found no evidence of corner monument. Reestablished corner mid-way and on-line between the section corners to the North and South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-10) 1/4 Corner Common to Sections 25 & 26, T. 46 N., R. 1 E.

Corner is a 3/4" x 24" re-bar with plastic Chippewa County Remonumentation Cap. Corner falls west of centerline of North-South (Lower Haylake) road.

Witnesses:			
8" Tamarack	N 50° E	114.11'	
Power Pole (DR1/76A/31)	S 53° E	51.45'	
10" Aspen	S 40° W	107.06'	
6" Tamarack	N 25° W	82.91'	

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by William L. Karr

Date 12-30-96

Surveyor's Michigan License No. 27450

