

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner \$7.00 LAND CORNER

For corners in

Chippewa County	Located in:			Corner Code #
Public Land Survey		T46N T T T	R1E R R R	K-12
Property Controlling	s	T	Ř	
in Section	s	T	R	
Miscellaneous	S	T	R	
Property in Sec.	S	T	R	

\$2.00 MSSR 2/28/1997 2:56:57 PM Receipt #217 RECEIVED FOR RECORD CHIPPENA COUNTY - STATE OF MICHIGAN SMARON H. KENNEDY, REGISTER OF DEEDS

100K 9 PAGE 357

10

Register of Deeds Stamp & File Number


4. Lot No.

, Recorded Plat

5. Private Claims

I, William L. Karr, in a field survey on November 28, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.



(K-12) 1/4 Corner Common to Sections 35 & 36, T. 46 N., R. 1 E.

J.H. Mullett set post in original survey.

1909 F.H. Brown in field book in County Surveyors Office states that Carleton had set section corners by dividing up the three miles from the NW corner of section 24, South to the township line. The notes show no evidence of 1/4 corners on this line.

1/4 corners on this line.

F.H. Brown in field notes in County Surveyors Office, show 2665' on the South 1/2 mile on the West side of 1910 section 36.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-12) 1/4 Corner Common to Sections 35 & 36, T, 46 N., R. 1 E.

E ONUMEN This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found 1/2" iron 3' West of centerline North-South gravel road. Position falls within 0.5' of being mid-way and on-line between the section corners to the North and South. Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-12) 1/4 Corner Common to Sections 35 & 36, T. 46 N., R. 1 E.

Corner is a 1/2" iron 3' West of centerline Lower Haylake Road.

Witnesses:

8" Spruce N 82° E 35.58 22" White Pine S 39° E 44.58 11" Jack Pine S 64° W 35.26' 16" Jack Pine N 41° W 43.66'



Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Date 12-30-96

Surveyor's Michigan License No. 27450

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS. JAN. 28. 1971 REVISED MAY 14, 1975 REVISED JAN., 1983 REVISED OCT., 1995