

CLERK'S OFFICE
CHIPPEWA COUNTY

MAR 26 1994

CHIPPEWA COUNTY REMONUMENTATION CORNER

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 30 PH 2:43

J. Roger Malott
REGISTER OF DEEDS

For corners in
Chippewa

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>45N</u> R <u>1E</u>	L-1 Same
	T <u>46N</u> R <u>1E</u>	L-13 Corner
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Keith R. Waters in a field survey on December 16, 1993

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

L-1 (T45N, R1E)
1/4 Corner Common to Section 1, T45N, R1E & Section 36, T46N, R1E.

Original ties to post: Birch 10, N47°W 31 links
Aspen 6, N31°E 15 links

Description of corner evidence found and/or method applied in restoring or reestablishing corner:


L-1 (T45N, R1E)
This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a 8" diameter concrete monument approximately 3 feet south of the centerline of east-west gravel road (12 Mile Road), 9 inches below gravel surface. Distance to Township corner east is 2652.73 feet and distance to Section corner west is 2654.70 feet. Corner is 20.59 feet south of a straight line between said Township and Section corners. Corner is on the approximate centerline of a woods road to the south. Accepted corner position as found and set a 3/4" rebar and plastic Chippewa County Remonumentation cap in the center of concrete monument, approximately 6 inches below surface of gravel road.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 (T45N, R1E)
Corner is a 3/4" x 24" rebar with plastic Chippewa County Remonumentation cap inside a 8" diameter concrete monument 3 feet south of the centerline of 12 Mile Road at the centerline of a woods road to the south. Witnesses:

- Power Pole, N63°W 84.67'
- 5" Black Ash, N30°E 65.90'
- 5" Balsam Fir, S07°E 48.78'
- 6" White Birch, S49°W 39.64'

Note: Distances are to a nail and tag in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination. Distances are measured with EDM.



Witnessed by Keith R. Waters Date 12-30-93
Surveyor's Michigan License No. 33142