

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Chippewa County Remonumentation Corner \$7.00 LAND CORNER

For corners **COMMISSION**

Chippewa County	Located in:	Corner Code #
1. Public Land Survey	T46N R1E T46N R2E T R T R T R	M-12 Same A-12 Corner
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No.	, Recorded Plat	
5. Private Claims		

\$2.00 MSSR
2/28/1997 2:47:05 PM Receipt #217
RECEIVED FOR RECORD
CHIPPewa COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 349

Register of Deeds Stamp & File Number

I, William L. Karr, in a field survey on December 4, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-12) 1/4 Corner Common to Section 36, T. 46 N., R. 1 E., and Section 31, T. 46 N., R. 2 E.

1845 J.H. Mullett set post in original survey.

1910 F.H. Brown in field notes in County Surveyors Office. Brown ran the line between sections 36 and 31 on a road. He shows the distance on the mile as 5324' and evenly divided.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-12) 1/4 Corner Common to Section 36, T. 46 N., R. 1 E., and Section 31, T. 46 N., R. 2 E.
This corner is being reestablished as part of the Chippewa County Remonumentation Program.

Found a 1/2" iron in the centerline, and a small pipe on the West edge of the North-South road, 2640' South of the N.E. corner of section 36. Testimony from property owner in the S.E. quarter of section 36 revealed that the iron was set by the people improving the south half mile of the road.

Overall mile measures 5319.84. Reestablished the 1/4 corner mid-way and on-line between the section corners to the North and South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-12) 1/4 Corner Common to Section 36, T. 46 N., R. 1 E., and Section 31, T. 46 N., R. 2 E.

Corner is a 3/4" x 24" re-bar with plastic Chippewa County Remonumentation Cap in centerline of North-South two track road.

Witnesses:	8" Spruce	S 52° E	34.56'
	20" Maple	S 55° W	56.60'
	9" Spruce	S 86° W	45.67'
	10" Maple	N 71° W	44.44'

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object unless otherwise noted.

Signed by William L. Karr

Date 12/30/96

Surveyor's Michigan License No. 27450

