

**SURVEY &
REMONUMENTATION**

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 27 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners **COMMISSION**

<u>Chippewa</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>46N</u> R <u>1W</u>	<u>A-5</u> same
	T <u>46N</u> R <u>2W</u>	<u>M-5</u> corner
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

\$ 7.00 LAND CORNER
\$ 2.00 MSSR
19 DEC 94 10:21 A.M. RECEIPT# 1769
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17		15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, William L. Karr, in a field survey on November 10, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-5) Section Corner 7 & 18, T.46 N., R.1 W. (Section Corner 12 & 13, T.46 N., R.2 W.)
1840: Austin Burt Spruce 4 S37W 04 lks Tamarack 7 N50W 16 lks
1845: J. Mullett Tamarack 12 N55E 18 lks Spruce 6 S22E 09 lks



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-5) This corner is being re-established as part of the Chippewa County Remonumentation program.
 Found no evidence of original corner. Re-constructed corner position 33.00' West of a North-South right-of-way fence for Townline Road and 33.00' North of the Southerly R.O.W. fence for an old grade going East between Sections 7 & 18. From the newly re-constructed corner there is an East-West 1/4 line fence in Section 18, 2653.44' to the South and East-West 1/4 line fences to the North which measure 2653.95'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-5) Corner is a 3/4"x 24" iron with plastic "Chippewa County Remonumentation" cap on the approximate centerline of Townline Road (gravel) and 23' North of the centerline of Forrest Side Road to the West.
 Witnesses: 4" W. Birch N22°E 87.18'
 10" Tamarack S35°E 160.88'
 P. Pole S15°W 219.70'
 P. Pole (DR4/74/17) N76°W 31.95'



Signed by William L. Karr Date 12/8/94

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination. Distances are to a nail in side of witness objects unless noted.