

**SURVEY &  
REMONUMENTATION**

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 27 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

| Chippewa<br>(County)                  | Located In:  | Corner Code #  |
|---------------------------------------|--|--|
| 1. Public Land Survey                 | T <u>46N</u> R <u>1W</u><br>T <u>46N</u> R <u>2W</u><br>T _____ R _____<br>T _____ R _____ | <u>A-8</u> same<br><u>M-8</u> corner<br>_____<br>_____ |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____<br>S _____ T _____ R _____   | _____<br>_____   |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____<br>S _____ T _____ R _____   | _____<br>_____   |
| 4. Lot No. _____, Recorded Plat _____ |  |  |
| 5. Private Claims _____               |  |  |

\$ 7.00 LAND CORNER  
\$ 2.00 MSSR  
19 DEC 94 10:21 A.M. RECEIPT# 1769  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, William L. Karr, in a field survey on November 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-8) 1/4 Corner Section 19, T.46 N., R.1 W. and Section 24, T.46 N., R.2 W.  
1840: Austin Burt set post Spruce 10 S08W 16  
Fir 6 N15W 13



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-8) This corner is being re-established as part of the Chippewa County Remonumentation program.  
Found no evidence of original corner. Re-established corner mid-way and on line between the Section Corner to the North and the Section Corner to the South. The re-established corner falls on the extension of a fenceline to the West. Distance to the North and South is 2630.20. Old County Surveyor notes (undated) show distances of 2632.5' for this line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-8) Corner is a 3/4"x 24" iron with plastic "Chippewa County Remonumentation" cap on the extension of a fenceline to the West.

|                     |       |         |
|---------------------|-------|---------|
| Witnesses: 7" Aspen | N49°E | 28.60'  |
| Corner fence post   | S64°E | 15.87'  |
| P. Pole             | S12°W | 172.72' |
| P. Pole             | N06°W | 154.94' |



Signed by William L. Karr Date 12/8/94

Surveyor's Michigan License No. 27450

723-12

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.