

**SURVEY &  
REMONUMENTATION**

CHIPPEWA COUNTY REMONUMENTATION CORNER

APR 27 1995

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>1W</u>	<u>A-10</u> same
	T <u>46N</u> R <u>2W</u>	<u>M-10</u> corner
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

\$ 7.00 LAND CORNER  
\$ 2.00 MSSR  
19 DEC 94 10:22 A.M. RECEIPT# 1769  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William L. Karr, in a field survey on November 10, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**


A. Description of original monument and accessories and/or subsequent restoration:

(A-10) 1/4 Corner Section 30, T.46 N., R.1 W. and Section 25, T.46 N., R.2 W.  
1840: Austin Burt set post Fir 10 N38E 13 lks  
Sugar 14 N11W 30 lks

- ? County Surveyor notes from the early 1900's show the West line of Section 30 measuring 2646' (2642.56' today) for the North 1/2 mile and 2633' (2631.13' today) for the South 1/2 mile.
- ? R.H. Larsen found or set the 1/4 corner in a private survey. It appears to be in the 1070's. He indicates a pipe at the corner with fencelines in both Sections.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-10) This corner is being perpetuated as part of the Chippewa County Remonumentation program.  
Found no evidence of original corner. Found a 3/4" iron on the extension of a fenceline to the West. I originally computed this position on a straight line between the Section corners to the North and South and on the extension of an old fenceline to the West. When we started to set the corner, we found an existing 3/4" iron. There is a large culvert in the area so magnetic location is not reliable. I accepted the position as found and set a remonumentation cap on the iron.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-10) Corner is a 3/4"x 24" iron with plastic "Chippewa County Remonumentation" cap on the approximate centerline of Townline Road (gravel).

Witnesses: 6" Ash	N51°E	43.63'
6" W. Pine	S23°E	73.79'
P. Pole (DR4/75/26)	S30°W	64.52'
8" Spruce	N10°W	107.41'



Signed by William L. Karr Date 12/8/94

Surveyor's Michigan License No. 27450

723-12

NOTE: Bearings are compass bearings corrected for declination.  
Distances are to a nail in side of witness objects unless noted.