

SURVEY &
REMONUMENTATION

Chippewa County Remonumentation Corner

RECEIVED FOR RECORD
CHIPPEWA COUNTY
STATE OF MICHIGAN

MAR 09 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 29 AM 10:24

For corners in
Chippewa
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>46N</u> R <u>1W</u> | <u>B-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

J. Roger Malott
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

T46N R1W

I, William L. Karr, in a field survey on May 24, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(B-1) North 1/4 Corner of Section 6 (T46N-R1W)

1985: William L. Karr, L.S. 27450, recorded in Liber 6, Page 371 of the Chippewa County Corner Records.
Reset 1/2" iron, L.S. 27450, in monument box.

4" White Birch	N19°E	68.09'
Power Pole (E 100)	S73°E	146.80'
Power Pole (E 101)	S68°W	118.93'
4" Spruce	N33°W	67.19'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B-1) This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found record corner and all four ties. Accepted corner as found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(B-1) Corner is a 1/2" iron, L.S. 27450, in monument box 0.5' North of the centerline of Six Mile Road.

Witnesses:

4" White Birch	N19°E	68.09'
Power Pole (E 100)	S73°E	146.69'
Power Pole (E 101)	S68°W	118.93'
4" Spruce	N33°W	67.11'
South 1/4 Corner Section 31	West	8.91'



Signed by William L. Karr Date 12/23/93

Surveyor's Michigan License No. 27450

NOTE: Bearings are compass bearings corrected for declination.
Distances are to a nail in side of witness objects unless noted.