

**SURVEY &
REMONUMENTATION**

MAY 28 1997

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 \$7.00 LAND CORNER

COMMISSION

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 1W	B-3
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

\$2.00 HSSR
2/28/1997 4:10:01 PM Receipt #226
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 389

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 12/18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3		●											
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-3 1/4 Corner Common to Sections 6 & 7, Town 46 North, Range 1 West

1845 - Original ties (James Mullett): Cedar 15, S20°E 30 links - Fir 10, N38°W 13 links.


1905 - County Surveyor Frederick H. Brown notes indicate that he found both original bearing trees and set a good cedar post. Distances to original section corners east and west are shown as 2605 feet and 2511 feet respectively.

1982 - William L. Karr, P.S. 27450, LCRC in liber 6, page 26. Set a 1/2" iron with cap #27450 at the base of a very old fence post. Fences run north, south, and east from this post. Witnesses: 6" Tamarack, N11°E 51.19' - 5" Spruce, N50°E 36.04' - Twin 6" White Birch, S71°E 77.75' - 14" White Birch, S29°W 61.80'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.

Found a 1/2" iron with a plastic cap #27450. Also found record witnesses shown as 6" tamarack and twin 6" birch on LCRC page 26, alive and in good condition. The spruce is standing but dead and the 14" birch is gone. The distances to section corners east and west check very well with those as shown in above mentioned Frederick H. Brown notes. I believe that the 1/2" iron is a perpetuation of the original corner location. Accepted corner as found and established additional witness objects.



C. Description of corner with monument and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" iron with a plastic cap #27450.

Witnesses:

10" White Birch, S71°E 78.00'

11" Tamarack, N11°E 51.10'

5" Balsam Fir, N47°W 17.00'

6" Balsam Fir, N51°E 12.10'



Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 9 PAGE 389