

**SURVEY & REMONUMENTATION**

MAY 28 1997

**CHIPPEWA COUNTY REMONUMENTATION CORNER**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 1W	B-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

\$7.00 LAND CORNER

\$2.00 MSSR

2/28/1997 4:17:32 PM Receipt #226  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 392

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 11/11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11	●											
12	31	32	33	34	35	36						
13												


A. Description of original monument and accessories and/or subsequent restoration:

B-11 1/4 Corner Common to Sections 30 & 31, Town 46 North, Range 1 West  
1845 - Original ties (James Mullett): Hemlock 12, S40°E 23 links - Spruce 12, N10°W 27 links.  
1891, 1899 - County Surveyor Frederick H. Brown notes indicate that he re-established this 1/4 corner and the section corner on the range line to the west at record GLO distances from an original section corner at C-11.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Chippewa County Remonumentation Program. Found no evidence of corner. Re-established corner on line between section corners east and west, on the extension of fence lines to the north and south. The east-west position fits well with both GLO and County Surveyor distances to section corners east and west. I believe that the fences were probably erected based on a corner re-established by Brown as described in above mentioned notes.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap approximately 2 feet north of the center of east-west gravel road (11 Mile Road), on the extension of fence lines north and south. Witnesses:  
Power Pole (DR4-39A-20), N83°E 386.71'  
Power Pole, N84°W 352.34'  
Power Pole (D62-33-21), N20°E 27.99'  
6" Tamarack, N18°W 247.27'

Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.

Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 9 PAGE 392