

**SURVEY &  
REMONUMENTATION**

**MAY 28 1997 CHIPPEWA COUNTY REMONUMENTATION CORNER**

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Chippewa Located In: Corner Code #  
(County)

- 1. Public Land Survey T46N R 1W C-6  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R



- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

\$7.00 LAND CORNER

\$2.00 MSSR  
2/28/1997 4:21:17 PM Receipt #226  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 9 PAGE 397

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on 12/06, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

C-6 1/4 Corner Common to Sections 17 & 18, Town 46 North, Range 1 West  
1845 - Original corner (James Mullett) was a 10" Spruce.

1915 - County Surveyor Frederick H. Brown notes indicate that this "1/4 post was gone." His sketch shows a distance of 5575 feet overall between sections 17 and 18.



**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

This corner is being re-established as part of the Chippewa County Remonumentation Program. Found no evidence of corner. Re-established corner on line between section corners north and south, at the intersection of the remains of an east-west fence line. The owner of the property both north and south of this corner, Mr. J. Hill, informed me that the property had been in his family for several generations and that the 1/4 post had always been assumed to be on the fence line. He also stated that he had tried to preserve the remaining posts. The distance from this re-established position to the section corner to the south in within 5 feet of a split of the distance as shown in above mentioned Frederick H. Brown notes. I believe that the fence is probably a result of a corner position as re-established by Brown, especially considering the large discrepancy on the overall mile with GLO notes (almost 300 feet).

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner is a 3/4" x 24" rebar with a stamped aluminum Chippewa County Remonumentation cap, on the remains of an east-west fence line.

Witnesses:

- Fence Post, S85°E 239.44'
- Fence Post, N85°W 8.02'
- Fence Post, N85°W 131.47'
- 14" White Oak, N87°W 149.90'

(Corner falls in a cultivated field and is buried 14" below ground surface).

Note: Distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination.

Trees are blazed and painted.

Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-06-96 PAGE 397