

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

CHIPPEWA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 1W	D-3
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

\$7.00 RECORDING FEE

\$2.00 NCSR

3/3/1997 4:59:51 PM Receipt #275
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 2

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 12/16, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3			●									
4	7		8		9		10		11		12	
5												
6	13		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- D-3 1/4 Corner Common to Sections 5 & 8, Town 46 North, Range 1 West
- 1845 - Original corner (James Mullett) was a 10" Fir.
- 1908 - County Surveyor Frederick H. Brown sketch indicates no original corner. Corner is shown midway between section corners 2623 feet east and west.
- 1995 - Certificate of Survey, Larry R. Rogers, P.S. 29251, shows found Bischer iron. Distances to section corners east and west are shown as 2627.92 feet and 2628.01 feet respectively.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found a 1/2" iron in the approximate centerline of an east-west 2 track seasonal road (7 Mile Road) as shown on above mentioned Certificate of Survey. Accepted corner location as found and replaced the 1/2" iron with a 3/4" x 24" rebar and plastic Chippewa County Remonumentation cap.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap in the approximate centerline of an east-west seasonal road (7 Mile Road). Witnesses:
 Fence Post, N42°E 36.75' (nail and tag #22428 in side)
 Fence Post, N52°E 52.58' (nail and tag #22428 in side)
 Fence Post, N70°E 85.25' (nail and tag #33142 in side)
 Fence Post, N78°E 123.45' (nail and tag #33142 in top)

Note: Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96



BOOK 10 PAGE 2