

SURVEY & REMONUMENTATION

MAY 28 1997 **CHIPPEWA COUNTY REMONUMENTATION CORNER**

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa Located In: Corner Code #
(County)

1. Public Land Survey T46N R 1W E-4
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R



\$7.00 RECORDING FEE

\$2.00 HSSR

3/3/1997 5:02:37 PM Receipt #275
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS
BOOK 10 PAGE 7

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Keith R. Waters, in a field survey on 10/31, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-4 1/4 Corner Common to Sections 8 & 9, Town 46 North, Range 1 West
1845 - Original ties (James Mullett): Spruce 12, S24°E 22 links - Spruce 12, S45°W 26 links.
1910 - County Surveyor Frederick H. Brown notes indicate that the corner was gone and that he divided the mile equally. Distances to section corners north and south are shown as 2630 feet.
1992 - Certificate of Survey, liber 605, page 602, Chippewa County records, shows a 1/2" rod at corner location. Witnesses: Fence Post, West 61.0' - Fence Post, N79°W 51.71' - Fence Post, N68°W 53.75' - Centerline of Road, West 1.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found a 1/2" iron in the centerline of a north-south gravel road (Maple Road), on the extension of an old fence line to the west, as shown in above mentioned Certificate of Survey. The distance to the section corner north is 2631.40 feet, distance to the section corner south is 2631.37 feet, and iron is 2.1 feet west of a straight line between said section corners. Distances are very close to those as shown in above mentioned Frederick H. Brown notes. Accepted corner position as found and replaced the 1/2" iron with a 3/4" x 24" rebar and plastic Chippewa County Remonumentation cap and established new witness objects.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" x 24" rebar with a plastic Chippewa County Remonumentation cap in the approximate centerline of a north-south gravel road (Maple Road), on the extension of a fence line to the west. Witnesses:
Power Pole, S44°W 60.93'
Power Pole, S20°E 234.73'
Power Pole, S55°E 55.04'
Power Pole, N07°E 161.76'

Note: Unless noted otherwise, distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96
BOOK 10 PAGE 7

