

**SURVEY &  
REMONUMENTATION**

MAY 28 1997 CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T46N R 1W	E-8
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

BOOK 10 PAGE 10

BOOK 10 PAGE 10  
RECORDING FEE

\$2.00 NGRS

3/3/1997 5:04:17 PM Receipt #275  
RECEIVED FOR RECORD  
CHIPPEWA COUNTY - STATE OF MICHIGAN  
SHARON H. KENNEDY, REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 08/22, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-8 1/4 Corner Common to Sections 20 & 21, Town 46 North, Range 1 West



1845 - Original corner (James Mullett) was a 10" Black Ash.

1905 - County Surveyor Frederick H. Brown notes indicate corner midway between section corners 2624½ feet north and south.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Chippewa County Remonumentation Program.

Found no evidence of corner. Re-established corner by single proportionate measurement on line between section corners 2623.5 feet north and 2623.5 feet south. Distances to said section corners are within 1 foot of above mentioned Frederick H. Brown notes.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a ¾" x 24" rebar with a plastic Chippewa County Remonumentation cap in the centerline of a north-south gravel road.

Witnesses:

Power Pole, S04°E 343.74'

Power Pole, N78°E 34.98'

Power Pole, N07°E 364.86'

(No other ties available)

Note: Distances are to a nail/tag #33142 in the side of the witness object. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 10