

SURVEY & REMONUMENTATION

MAY 28 1997 CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 1W	E-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$7.00 RECORDING FEE

\$2.00 N SSR

3/3/1997 5:04:49 PM Receipt #275
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 11

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 07/10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-9 Corner Common to Sections 20, 21, 28, & 29, Town 46 North, Range 1 West
1845 - Original ties (James Mullett): Fir 12, S34°W 33 links - Spruce 12, N13°E 12 links.
1903, 1905, 1907 - County Surveyor Frederick H. Brown notes indicate an original corner.
Circa 1920's - County Surveyor notes indicate cement post for corner with various witnesses.
1977 - James H. Granger, P.S. 16041, liber 1, page 273, Chippewa County corner records. Set 1/2" rod at proportionate distance from NE corner and north 1/4 corner (Section 28) according to a section subdivision by F.H. Brown.
1991 - William L. Karr, P.S. 27450, liber 7, page 384, Chippewa County corner records. Replaced corner as described in 1977 LCRC from existing survey control in area. Witnesses: Power Pole (DR4-39-16), S50°E 59.50' - Power Pole (DR4-39-15M), N70°W 149.84' - NE Edge of Stop Sign Base, N19°W 41.13' - Power Pole (DR4-39-15), N14°E 142.59' - Sawed off Pole with Box, N54°E 56.23'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program.
Found a 1/2" iron with cap #27450 and all witness objects as described in LCRC liber 7, page 384.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" iron with cap #27450 approximately 2.5 feet east of the centerline of Maple Road, approximately 1.3 feet south of the centerline of 10 Mile Road. Witnesses:
Power Pole (DR4-39-16), S50°E 59.50' (large nail in side)
Power Pole (DR4-39-15M), N70°W 149.84' (large nail in side)
Northeast Edge of Stop Sign Base, N19°W 41.13'
Power Pole, (DR4-39-15), N14°E 142.59'
Sawed off Power Pole with Box, N54°E 56.23'
Note: Unless noted otherwise, distances are to a nail/tag #27450 in the side of the witness object. Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96
BOOK 10 PAGE 11