

SURVEY & REMONUMENTATION

MAY 28 1997

CHIPPEWA COUNTY REMONUMENTATION CORNER

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 \$7.00 RECORDING FEE

For corners in
Chippewa

Located In: Corner Code #

(County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 1W	F-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

\$2.00 MSSR

3/3/1997 5:06:15 PM Receipt #275
RECEIVED FOR RECORD
CHIPPEWA COUNTY - STATE OF MICHIGAN
SHARON H. KENNEDY, REGISTER OF DEEDS

BOOK 10 PAGE 15

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Keith R. Waters 11/12 96

I, _____, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3						●							
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													


A. Description of original monument and accessories and/or subsequent restoration:

F-3 1/4 Corner Common to Sections 4 & 9, Town 46 North, Range 1 West

- 1845 - Original corner (James Mullett) was a 10" Fir.
- 1890 - County Surveyor Frederick H. Brown notes indicate corner midway between section corners 2690 feet east and west.
- 1982 - William L. Karr, P.S. 27450, LCRC in liber 7, page 3, Chippewa County corner records. Set corner in old road bed centerline between corner fence posts north and south. Set a 1" x 36" Drill Rod. Witnesses:
10" Poplar, N88°W 49.94' - 6" Poplar, N20°W 27.33' - 3" Birch, S40°W 34.13' - Corner Fence Post, North 30.0' - Corner Fence Post, South 30.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Chippewa County Remonumentation Program. Found a 1" drill rod as called for in LCRC liber 7, page 3. All the record witnesses are either missing or dead. Drill rod within 5.5 feet of a split between section corners east and west. The overall distance between said section corners is within 1.3 feet of above mentioned Brown notes. Accepted corner as found and established new witness objects.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1" drill rod in the centerline of an old east-west road bed.

- Witnesses:
- 3" Aspen, N06°E 18.17'
 - 4" Aspen, N08°W 22.25'
 - 3" Aspen, N34°W 22.35'
 - 3" Willow in Clump, N86°E 20.56'

Note: Unless noted otherwise, distances are to a nail and tag in the side of the witness object. Bearings are compass bearings corrected for declination. Trees are blazed and painted.



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96

BOOK 10 PAGE 15